



**ENGLEWOOD WATER DISTRICT**

201 Selma Ave  
Englewood, FL 34223  
(941) 474-3217

To: Prospective Bidders  
Date: August 18, 2021  
Re: **Addendum #2** to RFB 2021-124  
WTP Treater No. 2 Painting & Protective Coating

Bidders are notified that this Addendum will be made part of the bid documents. The intent of the Addendum is to add to, modify, or clarify the documents. Should any of these items have an effect on price, such changes shall be included in the bid price. These items have the same force and effect as if contained in the original documents.

Bidders are required to acknowledge receipt of this addendum in their bid forms.

**CLARIFICATION TO QUESTIONS ASKED/SPECIFICATIONS**

1. Q: What is the budget for this project?  
A: *The budget for the project is \$40,000.*
  
2. Q: Is this coating the interior of the tanks?  
A: *The services requested are for the painting and protective coatings for the inside of WTP Treater No. 2. It should be noted that the inside of the tank has lime scale which will need to be removed as part of the tank preparation.*
  
3. Clarification to Performance Time under Technical Specifications section (page 17):  
The equipment contractor will be mobilizing to the site on August 23, 2021 to demo the existing unit. The demo is expected to take approximately 2 weeks. Once demo is complete, the painting contractor will need to complete Phase 1. Once Phase 1 is completed, the equipment contractor will remobilize to install the new equipment. They are tentatively scheduled to return October 4, 2021. The equipment installation is expected to take 2-3 weeks. Once the equipment is installed, the painting contractor will need to complete Phase 2.
  
4. Clarification to required Protective Coatings:  
In all places where the document refers to "Series 20HS" shall be replaced with "Series 20".

*Bee Ling Wheaton*

Bee Ling Wheaton,  
Purchasing Manager